

Date Generated

Jun 8, 2022

Call Order

001

Project ID

1100990

Amendments

0

Counties

Sierra

Highway Number

Time Remaining

Add to calendar

Days

27

Hours

22

Description

Roadway Reconstruction, Bridge Replacement, Lighting

Items

Favorite items only

Line	Item	Description	Unit	Quantity	Price
Section 0001: ROADWAY					
0010	201000	CLEARING AND GRUBBING	LS	1	
0020	203000	UNCLASSIFIED EXCAVATION	C.Y.	383500	
0030	203100	BORROW	C.Y.	222750	
0040	203211	UNSTABLE SUBGRADE STABILIZATION	S.Y.	10150	
0050	207000	SUBGRADE PREPARATION	S.Y.	58600	
0060	303000	BASE COURSE	TON	17530	

Line	Item	Description	Unit	Quantity	Price
0070	303160	BASE COURSE 6"	S.Y.	3810	
0080	403715	RUBBERIZED OPEN-GRADED FRICTION COURSE COMPLETE	TON	1110	
0090	405000	DETOUR PAVEMENT CONSTRUCTION	S.Y.	11100	
0100	407000	ASPHALT MATERIAL FOR TACK COAT	TON	51	
0110	408100	PRIME COAT MATERIAL	TON	99	
0120	414000	COLD MILLING (ASPHALT)	SYIN	119900	
0130	423283	HMA SP-IV COMPLETE	TON	23300	
0140	502030	DRILLED SHAFT FOUNDATION 30" DIAMETER	L.F.	263	
0150	502054	DRILLED SHAFT FOUNDATION 54" DIAMETER	L.F.	33	
0160	511030	STRUCTURAL CONCRETE, CLASS AA	C.Y.	1510	
0170	515000	REINF.CONCRETE FOR MINOR STRUCTURES	C.Y.	340	
0180	540060	REINFORCING BARS GRADE 60	LB	338537	
0190	570437	24" STORM DRAIN CULVERT PIPE	L.F.	1220	
0200	570441	24" STORM DRAIN CULVERT PIPE END SECTION	EACH	7	
0210	570449	30" STORM DRAIN CULVERT PIPE	L.F.	420	
0220	570453	30" STORM DRAIN CULVERT PIPE END SECTION	EACH	1	
0230	570461	36" STORM DRAIN CULVERT PIPE	L.F.	220	
0240	570465	36" STORM DRAIN CULVERT PIPE END SECTION	EACH	1	
0250	570473	48" STORM DRAIN CULVERT PIPE	L.F.	380	
0260	570477	48" STORM DRAIN CULVERT PIPE END SECTION	EACH	6	
0270	570486	60" STORM DRAIN CULVERT PIPE	L.F.	440	
0280	570491	60" STORM DRAIN CULVERT PIPE END SECTION	EACH	2	
0290	570507	78" STORM DRAIN CULVERT PIPE	L.F.	40	
0300	570512	78" STORM DRAIN CULVERT PIPE END SECTION	EACH	1	
0310	601000	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	1	
0320	601110	REMOVAL OF SURFACING	S.Y.	44200	
0330	602000	RIPRAP CLASS A	C.Y.	630	
0340	602060	RIPRAP CLASS G	S.Y.	74730	
0350	603100	TEMPORARY SOIL STABILANT	ACRE	27	

Line	Item	Description	Unit	Quantity	Price
0360	603262	COMPOSTED MULCH SOCKS	L.F.	11200	
0370	603281	SWPPP PLAN PREPARATION AND MAINTENANCE	LS	1	
0380	606001	SINGLE FACE W-BEAM GUARDRAIL	L.F.	2837.5	
0390	606051	END TREATMENT TL-3 END TERMINAL	EACH	8	
0400	606053	END TREATMENT W-BEAM END ANCHOR	EACH	7	
0410	606062	TRANSITION METAL BARRIER TO RIGID BARRIER	EACH	13	
0420	606542	CONCRETE WALL BARRIER 42"	L.F.	2886	
0430	606554	CONCRETE WALL BARRIER 54"	L.F.	201	
0440	606598	TCWB RETAINED BY THE CONTRACTOR	L.F.	12400	
0450	606599	RESETTING OF TCWB	L.F.	23920	
0460	607010	BARBED WIRE FENCE (GAME FENCE) 4'	L.F.	6920	
0470	607015	BRACES/CORNER POSTS	EACH	395	
0480	607312	STANDARD GATE, 12'	EACH	2	
0490	608404	CONCRETE MEDIAN PAVEMENT 4" (COLORED AND PATTERNED)	S.Y.	120	
0500	609324	CONCRETE SLOPED CURB AND GUTTER 6" X 24"	L.F.	7030	
0510	609424	CONCRETE VERTICAL CURB AND GUTTER TYPE B 6" X 24"	L.F.	2490	
0520	609478	CONCRETE VERTICAL CURB AND GUTTER TYPE D 6" X 18"	L.F.	1890	
0530	617000	VIBRATION MONITORING	LS	1	
0540	617002	AERIAL PROGRESS PHOTOS	LS	1	\$26,000.00
0550	617004	VIBRATION RISK SURVEY	LS	1	
0560	618000	TRAFFIC CONTROL MANAGEMENT	LS	1	
0570	618011	PUBLIC AWARENESS	LS	1	\$6,000.00
0580	620000	SELECTIVE/NON-SELECTIVE HERBICIDE APPLICATION	ACRE	17	
0590	621000	MOBILIZATION	LS	1	
0600	623039	MEDIAN DROP INLET TYPE III (RURAL)	EACH	1	
0610	623114	MEDIAN DROP INLET 5'X5' (RURAL) H=3'1" TO 6'0"	EACH	6	
0620	623115	MEDIAN DROP INLET 5'X5' (RURAL) H=6'1" TO 9'0"	EACH	1	
0630	623116	MEDIAN DROP INLET 5'X5' (RURAL) H=9'1" TO 12'0"	EACH	2	
0640	623117	MEDIAN DROP INLET 5'X5' (RURAL) H=12'1" TO 15'0"	EACH	1	

Line	Item	Description	Unit	Quantity	Price
0650	623331	CURB DROP INLET TYPE I-B, OVER 4'	EACH	1	
0660	623404	DROP INLET 4'X4' (TYPE I) H=4'-1" TO 6'-0"	EACH	1	
0670	623407	DROP INLET 4'X4' (TYPE I) H=6'-1" TO 8'-0"	EACH	3	
0680	631000	RUMBLE STRIPS	L.F.	10600	
0690	632000	CLASS A SEEDING	ACRE	19	
0700	632020	CLASS C SEEDING	ACRE	5	
0710	667210	LANDSCAPE GRAVEL	S.Y.	1610	
0720	701000	PANEL SIGNS	S.F.	900	
0730	701010	EXTRUDED PANEL SIGNS	S.F.	655	
0740	701030	REMOVE AND RESET PANEL SIGN	EACH	1	
0750	701040	REMOVE AND RESET EXTRUDED PANEL SIGN	EACH	1	
0760	701100	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	L.F.	1485	
0770	701108	STEEL I-BEAM POST TY S4X7.7	L.F.	50	
0780	701109	STEEL I-BEAM POST TYPE W6X9	L.F.	5	
0790	701121	STEEL I-BEAM POST TYPE W8X21	L.F.	35	
0800	701208	BREAKAWAY BASE SYSTEM FOR STEEL I BEAM POST S4X7.7	EACH	4	
0810	701221	BREAKAWAY BASE SYSTEM FOR STEEL I BEAM POST W8X21	EACH	2	
0820	701451	OVERHEAD SIGN STRUCTURE, CANTILEVER TYPE, 30-INCH	EACH	1	
0830	702000	CONSTRUCTION SIGNING	S.F.	1586	
0840	702100	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	L.F.	5738	
0850	702101	MULTI-DIRECTIONAL SLIP BASE POSTS FOR CONSTRUCTION SIGNING	EACH	12	
0860	702238	BARRICADE, TYPE III-8'	EACH	13	
0870	702525	CHANNELIZATION DEVICES TYPE DRUM	EACH	280	
0880	702600	SEQUENTIAL ARROW DISPLAY	EACH	3	
0890	702610	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	5	
0900	702613	SPEED DETECTOR RADAR TRAILER	EACH	2	
0910	702850	LAW ENFORCEMENT IN CONSTRUCTION ZONE	ALOW	1	\$30,000.00
0920	704000	RETROREFLECTORIZED PAINTED MARKINGS 4"	L.F.	18600	
0930	704099	TEMPORARY RETROREFLECTORIZED PAINTED MARKINGS 4"	L.F.	111400	

Line	Item	Description	Unit	Quantity	Price
0940	704717	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW	EACH	6	
0950	704718	HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	EACH	2	
0960	704720	HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	EACH	3	
0970	704735	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT LANE DROP ARROW	EACH	6	
0980	704760	DOUBLE DROP HOT THERMOPLASTIC PAVEMENT MARKINGS 4"	L.F.	7100	
0990	704761	DOUBLE DROP HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	L.F.	25900	
1000	704763	DOUBLE DROP HOT THERMOPLASTIC PAVEMENT MARKINGS 12"	L.F.	6600	
1010	704856	REFLECTIVE RAISED PAVEMENT MARKER TYPE C	EACH	60	
1020	704869	PLOWABLE REFLECTIVE RAISED PAVEMENT MARKER TYPE PG	EACH	99	
1030	704876	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TG	EACH	640	
1040	704877	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TH	EACH	570	
1050	704939	PREFORMED THERMOPLASTIC PAVEMENT MARKING WRONG WAY ARROW	EACH	4	
1060	705000	SIGNAL/LIGHTING SYSTEM START-UP COSTS	ALOW	1	\$19,000.00
1070	706010	SERVICE POLE (LIGHTING)	EACH	1	
1080	706110	SERVICE RISER (LIGHTING)	EACH	1	
1090	706420	LIGHTING CONTROL CABINET-TWO CIRCUIT	EACH	1	
1100	707540	TYPE V STANDARD, 40'	EACH	35	
1110	709020	RIGID ELECTRICAL CONDUIT 2" (DIA.)	L.F.	10475	
1120	710000	ELECTRICAL PULL BOX (STANDARD)	EACH	30	
1130	711102	SINGLE CONDUCTOR 2	L.F.	20950	
1140	716000	LIGHTING SYSTEM	LS	1	
1150	716701	LED ROADWAY LUMINAIRE	EACH	39	
1160	720060	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	EACH	4	
1170	720110	REMOVE/RESET IMPACT ATTENUATOR UNIT	EACH	7	
1180	721000	REMOVAL OF PAVEMENT MARKING	L.F.	82580	
1190	801000	CONSTRUCTION STAKING BY THE CONTRACTOR	LS	1	
1200	802000	POST CONSTRUCTION PLANS	LS	1	\$6,000.00
1210	803000	SCHEDULE SOFTWARE	LS	1	

Line	Item	Description	Unit	Quantity	Price
1220	803010	CPM TRAINING	LS	1	
1230	803020	CPM HARDWARE/EQUIPMENT	LS	1	
Section 0002: BRIDGE					
1240	210002	MAJOR STRUCTURE EXCAVATION	C.Y.	799	
1250	210003	MAJOR STRUCTURE BACKFILL	C.Y.	2752	
1260	411000	HOT POURED CRACK SEALING	LB	48	
1270	501100	PILE SPLICES	EACH	3	
1280	501101	PILE CUT-OFFS	L.F.	105	
1290	501124	DRIVEN PILES (24" PIPE)	L.F.	2090	
1300	504301	PILE DYNAMIC TEST CONSULTANT TESTING	EACH	3	
1310	504401	CASE PILE WAVE ANALYSIS TEST CONSULTANT TESTING	EACH	6	
1320	511000	STRUCTURAL CONCRETE, CLASS A	C.Y.	629	
1330	511070	STRUCTURAL CONCRETE, CLASS HPD	C.Y.	288	
1340	514042	CONCRETE BARRIER RAILINGS 42"	L.F.	451	
1350	540060	REINFORCING BARS GRADE 60	LB	121392	
1360	540061	GALVANIZED BARS GRADE 60	LB	83254	
1370	541100	STRUCTURAL STEEL FOR STEEL BRIDGES	LB	106347	
1380	560000	ELASTOMERIC BEARING PADS	EACH	20	
1390	562000	BRIDGE JOINT STRIP SEAL	L.F.	77	
1400	563099	POLYMER BRIDGE JOINT SEALS	L.F.	73	
1410	601000	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	1	
1420	604003	GEOTEXTILE CLASS 3	S.Y.	4702	
1430	604300	GEOGRID REINFORCEMENT	S.Y.	11960	
1440	667003	ARTWORK COMPLETE	LS	1	

Showing **144** items

Letting of Jul 15, 2022: 2 of 2

Date Generated

Jun 8, 2022

Call Order

002

Project ID

5101120

Amendments

0

Counties

San Juan

Highway Number

Time Remaining

Add to calendar

Days

27

Hours

22

Description

Roadway Reconstruction, Lighting, ITS

Items

Favorite items only

Line	Item	Description	Unit	Quantity	Price
------	------	-------------	------	----------	-------

Section 0001: ROADWAY

Line	Item	Description	Unit	Quantity	Price
0010	201000	CLEARING AND GRUBBING	LS	1	
0020	203000	UNCLASSIFIED EXCAVATION	C.Y.	2090	
0030	203100	BORROW	C.Y.	10	
0040	203211	UNSTABLE SUBGRADE STABILIZATION	S.Y.	340	
0050	207000	SUBGRADE PREPARATION	S.Y.	6700	
0060	303000	BASE COURSE	TON	2150	
0070	405000	DETOUR PAVEMENT CONSTRUCTION	S.Y.	200	
0080	407000	ASPHALT MATERIAL FOR TACK COAT	TON	3	
0090	408100	PRIME COAT MATERIAL	TON	14	
0100	416106	MINOR PAVING TYPE I, HMA SP-III	S.Y.	4970	
0110	416206	MINOR PAVING TYPE II, HMA SP-III	S.Y.	980	
0120	502030	DRILLED SHAFT FOUNDATION 30" DIAMETER	L.F.	75	
0130	511000	STRUCTURAL CONCRETE, CLASS A	C.Y.	5	
0140	540060	REINFORCING BARS GRADE 60	LB	2551	
0150	570024	24" CULVERT PIPE	L.F.	230	
0160	601000	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	1	
0170	601110	REMOVAL OF SURFACING	S.Y.	7590	
0180	603100	TEMPORARY SOIL STABILANT	ACRE	4	
0190	603262	COMPOSTED MULCH SOCKS	L.F.	675	
0200	603281	SWPPP PLAN PREPARATION AND MAINTENANCE	LS	1	
0210	607014	WOVEN WIRE FENCE 4'	L.F.	4153	
0220	607015	BRACES/CORNER POSTS	EACH	20	
0230	607024	CHAIN LINK FENCE 4'	L.F.	206	
0240	607251	REMOVE AND RESET GATE	EACH	2	
0250	607404	CHAIN LINK GATE, 4' (SPAN)	EACH	1	
0260	607416	CHAIN LINK GATE, 16' (SPAN)	EACH	1	
0270	608004	CONCRETE SIDEWALK 4"	S.Y.	30	
0280	610000	CATTLE GUARD	L.F.	32	
0290	613000	CLEANING CULVERTS AND DRAINAGE STRUCTURES	LS	1	

Line	Item	Description	Unit	Quantity	Price
0300	614002	PIPE CASING 2"	L.F.	110	
0310	618000	TRAFFIC CONTROL MANAGEMENT	LS	1	
0320	618011	PUBLIC AWARENESS	LS	1	\$5,000.00
0330	621000	MOBILIZATION	LS	1	
0340	622002	FIELD LABORATORY, TYPE II	EACH	1	
0350	622100	SUPPLEMENTAL FIELD LABORATORY	EACH	1	
0360	622110	SUPPLEMENTAL HOT-MIX ASPHALT FIELD LABORATORY	EACH	1	
0370	622300	FIELD LABORATORY TESTING EQUIPMENT	LS	1	\$50,000.00
0380	623027	MEDIAN DROP INLET TYPE II (RURAL)	EACH	1	
0390	632000	CLASS A SEEDING	ACRE	3	
0400	632020	CLASS C SEEDING	ACRE	1	
0410	701000	PANEL SIGNS	S.F.	395	
0420	701031	REMOVE AND RESET TRAFFIC SIGN	EACH	2	
0430	701100	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	L.F.	587	
0440	702000	CONSTRUCTION SIGNING	S.F.	196	
0450	702100	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	L.F.	108	
0460	702101	MULTI-DIRECTIONAL SLIP BASE POSTS FOR CONSTRUCTION SIGNING	EACH	12	
0470	702610	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2	
0480	702810	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	LS	1	
0490	704000	RETROREFLECTORIZED PAINTED MARKINGS 4"	L.F.	27090	
0500	704009	RETROREFLECTORIZED PAINTED MARKING RIGHT ARROW	EACH	2	
0510	704010	RETROREFLECTORIZED PAINTED MARKING LEFT ARROW	EACH	2	
0520	704012	RETROREFLECTORIZED PAINTED MARKING WORD (ONLY)	EACH	2	
0530	704100	REMOVABLE MARKING TAPE 4"	L.F.	5000	
0540	704735	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT LANE DROP ARROW	EACH	2	
0550	704736	HOT THERMOPLASTIC PAVEMENT MARKING LEFT LANE DROP ARROW	EACH	2	

Line	Item	Description	Unit	Quantity	Price
0560	706010	SERVICE POLE (LIGHTING)	EACH	1	
0570	706110	SERVICE RISER (LIGHTING)	EACH	1	
0580	706350	POWER SERVICE INSTALLATION	LS	1	\$10,500.00
0590	706420	LIGHTING CONTROL CABINET-TWO CIRCUIT	EACH	1	
0600	707540	TYPE V STANDARD, 40'	EACH	10	
0610	709020	RIGID ELECTRICAL CONDUIT 2" (DIA.)	L.F.	2425	
0620	710000	ELECTRICAL PULL BOX (STANDARD)	EACH	6	
0630	711102	SINGLE CONDUCTOR 2	L.F.	5850	
0640	715011	SOLAR POWERED RADAR FEEDBACK UNIT	EACH	2	
0650	716701	LED ROADWAY LUMINAIRE	EACH	10	
0660	721000	REMOVAL OF PAVEMENT MARKING	L.F.	5000	
0670	750032	MULTI-DUCT CONDUIT 2" (8-WAY)	L.F.	5702	
0680	750060	ITS PULLBOX (33"X24"X24")	EACH	10	
0690	750080	ITS MANHOLE (48"X48"X48")	EACH	1	
0700	801000	CONSTRUCTION STAKING BY THE CONTRACTOR	LS	1	
0710	802000	POST CONSTRUCTION PLANS	LS	1	\$5,000.00
0720	803000	SCHEDULE SOFTWARE	LS	1	

Showing **72** items