



→ Mark L. Pickering, P.E.  
Senior Project Manager


# Owner's Advisor (OA)

Advantages and Case Study

# Welcome

1

## Agenda



Collaborative Delivery

OA Roles

When to Consider OA

Benefits

Qualifications

Case Study – PSU WRF

“The role of the OA for collaborative delivery projects holds a unique position relative to traditional engineering and program management scopes of services. An OA is focused on the strategy, tactics, and implementation of a successful collaborative delivery project.” -WCDA


2

© 2024 GHD. All rights reserved.

2

## What is Collaborative Delivery

- Collaborative effort
- Design to be built – not bid
- Opportunity to realize and share savings




About 47% of Construction \$\$ 2022-2026

Alternate Project Delivery

3


## Why collaborative delivery?



Alternate Project Delivery


4

## Where is the best OA fit?



5

## Owners Advisor Roles



6

### Feasibility and Planning

- Funding Approach and Project Budget
- Project Definition and Permitting Needs
- Selecting Collaborative Delivery Team

### Technical Services

- Specialty Technical Expertise
- Conceptual/Preliminary Design
- Detailed Design Criteria
- Collaborative Design and Constructability Review
- Opinion of Cost

### Procurement and Implementation

- Bid Documents
- Bid evaluation and procurement assistance
- Key submittals review and RPR services
- Commissioning

I © 2024 GHD. All rights reserved.

6

## When to Consider an Owner's Advisor

- limited collaborative delivery experience
- limited internal resources
- limited procurement and technical expertise
- significant size
- significant complexity
- complex funding/regulatory requirements
- budget constraints
- construction oversight
- startup and commissioning assistance



PA-AWWA 2025 Spring | © 2024 GHD. All rights reserved.

7

7

## Benefits of having OA



Design and Treatment Performance



Administrative/Permit Performance



Delivery Performance (Construction)



Operational Performance



Life Cycle Performance

### Checks and Balances

Schedule Deadlines and Milestones  
 Interpretation of Performance Guarantee  
 LDs OR Incentives  
 Progress Payments for Milestones  
 Nonconforming Work



8

8

## OA Qualifications

OA is not the  
engineer of  
record

Experienced in  
Collaborative  
Delivery

Technical  
Expertise

Construction  
Experience

Risk  
Management

Startup and  
Operations


State/Local  
Statutes and  
Agencies

9

[Footer] | © 2024 GHD. All rights reserved.

9

## OA Case Study PSU University Park WRF



Serves all University Park



- Site treatment beginning in 1913
- Majority of processes constructed in 1950's and 1960's
- Past Average treatment of 1.6 MGD
- Living Filter Recharge

10



## Improved infrastructure



Structural Deficiencies


50-year treatment horizon

All upgrades to improve safety to employees and students

Treatment Limitations

11

## WRF Upgrade Program



- June 2010 Process Evaluation Report
- August 2015 Basis of Design Report
- Budget of \$46 million
- Design Capacity 2.5 MGD
- Wholly funded by PSU (Private)
- Decision for Alternate Project Delivery (APD) – Design/Build

	MBR	BioMag®	IFAS
Estimated Capital Cost of Alternatives <sup>1</sup>	\$21,100,000	\$19,500,000	\$19,300,000
Estimated Capital Costs of Common Elements <sup>2</sup>	\$19,000,000	\$19,000,000	\$19,000,000
Engineering, Administration, and Legal Costs	\$6,200,000	\$6,200,000	\$6,200,000
<b>ESTIMATED TOTAL PROJECT COST</b>	<b>\$46,300,000</b>	<b>\$44,700,000</b>	<b>\$44,500,000</b>

12

## PSU "third party" scope\*

Extension of owner representation for:

1. Value Engineering
  - a. Site facility report
  - b. Technology selection
  - c. Act 537 Plan
2. Design Document Reviews and Review Meetings
3. Cost estimate review at 30%, 60%, 90%
4. Achieve program goals of reliability, consistency, level of detail, scope inclusion, and market comparison
5. Review GMP with specific feedback on contract details and outstanding items

\*Selection of GHD was through competitive process

13

## PSU WRF at 30% Design

### 30% Design and Value Engineering

- Build size and peak factors
- Equipment redundancy and risk
- Need for PTF Building
- Type of MBR
- Disinfection and UW
- Accessibility and safety
- Third party pricing comparison
- Direct and indirect costs Estimates qualified to vary 10-15% on average
- Estimated construction period 36-40 months
- Cost review within margin of error



30% Design Level Budget	
Revised 30% Design Estimate	\$64,466,293
Engineer's Opinion of Probable Cost	\$53,920,000
Low End Estimate (-10%)	\$48,528,000
High End Estimate (+20%)	\$64,704,000

reserved.

14

14


## Site accessibility was key consideration

Ingress/Egress for:

Construction

Operations

Staff and Students



15

## VE Review

	Accepted 30% Value Engineering
(\$2,100,000)	Eliminate UV Disinfection Facility
(\$1,300,000)	Reduction of Construction Schedule by 6 Months - related to removal of UV Facility scope
(\$500,000)	Reduction of On Site Staffing
(\$150,000)	Exterior stair at PTF building
(\$250,000)	Split Face Block in Lieu of Brick Veneer - PTF
(\$190,000)	Split Face Block in Lieu of Brick Veneer - MBR
(\$250,000)	Reduce size of pipe gallery - MBR
(\$150,000)	Blowers on exterior pad
(\$80,000)	Shelf spare permeate and drain pumps
(\$770,000)	Eliminate Separate Thickener Facility
(\$560,000)	Allow 480V Pumps at Effluent Pump Station
(\$6,300,000)	

Ref.	Description
<b>300 – Biological Reactor Basins (BRB) and Membrane Bioreactor (MBR) Structure</b>	
300.1	Eliminate swing zone
300.2	Eliminate pipe gallery (no step feed)
300.3	Remove the enclosed stairs
300.4	Blowers moved to outside pad
300.5	Remove superstructure over MBR tanks
300.6	Removal of backpulse tank
300.7	Eliminate spare permeate pump for shelf spare
300.8	Use butterfly valves for permeate lines
300.9	Eliminate spare MBR drain pump for shelf spare

Ref.	Description
<b>400 – UV Disinfection</b>	
400.1	Eliminate UV Disinfection facility
400.2	Move UV facility to BRB/MBR facility and have only one channel
400.3	Provide NPW supply from effluent PS force main
400.4	Enlarge footprint and reduce excavation

16



## PSU WRF at 60%

### 60% Design

- VE recap/additional VE
- Cost estimate and scope
- Risk register review
- Procurement Method(bid GC packages)

30% Design Level Budget	
Revised 30% Design Estimate	\$64,466,293
Net VE Deducts	\$- 6,300,000
Total With VE Deducts	\$58,166,293
Planning Budget	\$46,300,000




17

## PSU Risk Register

### Contingency Items

- Subcontracts
- Liability
- Liquidated Damages
- Design Items
- Permitting
- Construction

Updated through GMP

B		C		E		F		G		H		I		J	
 <b>HASKELL</b>		Date: 05/11/18 Job #: 6703660 Name: University Park WWTP													
No.	Risk Issue	Potential Cause	Exposure	Mitigation	Mitigation \$ Allocation	Cost of Mitigation	Remaining Exposure (less Mitigation)	Contingency %	Contingency						
B. Design															
B.1	Construction Management Administration through GMP	Personnel costs not included in Pre-Con Change Orders	\$350,000	Tracking Costs that could be lost if the project is cancelled.	None included in direct costs.	\$0	\$350,000	100%	\$350,000						
B.2	Lacking information from Geotech Report	Not enough borings to properly locate rock strata	\$0	Clarification in GMP summary.		\$0	\$0	0%	\$0						
B.3	Missing scope sitework.	Design is only 60%	\$2,800,000	Assign contingency accordingly for design completion percentage	\$0	\$0	\$2,800,000	15%	\$420,000						
B.4	Missing scope Electrical	Design is only 60%	\$1,740,000	Assign contingency accordingly for design completion percentage	\$0	\$0	\$1,740,000	20%	\$348,000						
B.5	Missing scope HVAC	E-finity Distributed Generation This product should be considered at the WWTP project. It can use natural gas or biogas to generate electricity, and the waste heat can be used to supplement the WWTP processes as well as run a absorber to cool the admin building.	\$320,000	Assign contingency accordingly for design completion percentage	\$0	\$0	\$320,000	25%	\$80,000						
B.6	Missing scope Plumbing	Currently no design, only fixtures have been shown	\$64,000	Assign contingency accordingly for design completion percentage	\$0	\$0	\$64,000	75%	\$48,000						
	Missing Fire Protection	Currently no design, only fixtures have been shown, fire pump?	\$100,000	Assign contingency accordingly for design completion percentage	\$0	\$0	\$100,000	100%	\$100,000						

18

## PSU Early procurement

### MBRs

- Competitive procurement
- Selected Hollow Fiber MBR

### Thickener

- In Primary Digester Control Bldg.
- Employee Trailers
- Temporary Relocation



19

## OA 90% Design quality check

GHD Design Review Document Comment Tracker

### All Disciplines

### Recorded Responses

### Backcheck of High Risk Items

Document Under Review: PSU 90% Design Uploaded 9/12/18				As of: 9/24/2018		
Design Comment #	Discipline	Page or Process Area	Made By	GHD COMMENT	DISPOSITION	Made By
MP-018	Mech/Process	PTF	J.Kostelac	Yard piping associated with odor control (drains, NPW, etc.) should be shown on the piping plan.	Corrected	J Hartwig
MP-019	Mech/Elect/I&C	PTF	J.Kostelac	There appears to be some disagreement in the number of BRB and MBR blowers provided between the M drawings, I drawings, E drawings and Evoqua package.	This is not the PTF. Coordination has been completed for the BRB and MBR blowers with Evoqua	J Hartwig
MP-020	Mech/Process	M150 & M151	J.Kostelac	Why not combine all three modified EQ tanks to one EQ tank? Per 30% review, the total converted EQ tank capacity is only 0.45 mgd. It may not be necessary to keep them as separate tanks with multiple inlets and outlets as well as multiple level control systems.	Separate tanks are provided for flexibility and reduce effort for cleaning	J Hartwig
MP-021	Mech/Process	M152	J.Kostelac	The three 12" slide gates and piping are new and they should be shown with heavy lines.	Corrected	J Hartwig
MP-022	Mech/Process	M152	J.Kostelac	Are these slide gates necessary?	Yes to provide tank isolation	J Hartwig
MP-023	Mech/Process	M152	J.Kostelac	How to keep solids in suspension?	Not necessary based on an approved previous decision	J Hartwig
MP-024	Mech/Process	M152	J.Kostelac	How are the EQ Return Pumps controlled?	Magnetic flow meter and control valve	J Hartwig
MP-025	Mech/Process	M153	J.Kostelac	Why only fill half of all the existing sludge hoppers with concrete fill? They all should be filled.	Corrected. Both are being filled	J Hartwig
MP-026	Mech/Process	M300	J.Kostelac	Update M300 to match other mechanical drawings (e.g., pumping equipment in the MBR building shown on DWG M300 is not consistent with those shown on DWGs M310 and M319)	Drawings are updated to finalize the design	D. Baar
MP-027	Mech/Process	M300	J.Kostelac	Remove air ducts and roofing shown above Electrical Room on DWGs M300 and M302 for better view.	Drawings are updated to finalize the design	D. Baar

20

## PSU GMP 1 Review

Started November 2018  
 2 Contracts for Demolition,  
 Temporary/Bypass, New Connections  
     Site Utilities – Process  
     Electrical Utilities  
 D/B Nonconstruction Costs  
 Market Procurement of Contracts  
 Critical Bypassing during PSU Winter  
 Break  
 Ongoing demolition phase



21

## PSU Bid packages

25 Separate Packages  
 Advertised on PSU OPP Site  
 Managed by D/B Team  
 Bidders Descoped  
 Comparison to 90% Estimate  
 Recommendation to PSU

Some packages received no bids  
 Third Party Team asked to assist  
 Packages 5 and 15

### Stages 3, 4 & 5 WRF Upgrades

Haskell General Conditions  
 Bid Package 02.3 - Landscaping & Grassing  
 Bid Package 02.4 - Fencing  
 Bid Package 02.5 - Site Utilities  
 Bid Package 02.6 - Earthwork  
 Bid Package 02.7 - Paving  
 Bid Package 03.0 - Concrete  
 Bid Package 03.4 - Post Tension Concrete Tank  
 Bid Package 04.0 - Masonry  
 Bid Package 05.0 - Metals \*\*\*Haskell Bidding\*\*\*  
 Bid Package 07.0 - Metal Roofing and Wall Panels  
 Bid Package 08.0 - Doors and Windows  
 Bid Package 08.1 - Overhead Coiling Doors  
 Bid Package 08.2 - Admin Bldg COMPLETE  
 Bid Package 09.0 - Painting & Coatings  
 Bid Package 09.1 - Building Finishes (PTF & MBR)  
 Bid Package 10.0 - Specialties  
 Bid Package 11.0 - Process Equipment  
 Bid Package 12.0 - Laboratory  
 Bid Package 14.0 - Cranes & Hoists  
 Bid Package 15.0 - Process Piping\*\*\*Haskell Bidding\*\*\*  
 Bid Package 15.1 - Plumbing  
 Bid Package 15.2 - HVAC  
 Bid Package 15.3 - Fire Protection  
 Bid Package 16.0 - Electrical  
 Bid Package 17.0 - I&C

22

## OA Bid Package Review

### GMP and Procurement

- Phases 1 and 2 GMP
- Construction value market pricing
- Bid Package Evaluation

Bidder	Form of Proposal	Bid Guarantee	Receipt of Addenda	General Acknowledgments	Staffing Plan	DBE Utilization Form	Public Works Employment Verification	Prequalified by Haskell
The Haskell Company	Yes	No	Yes	Yes	No	No	No	Yes
GM McCrossin	Yes	No	Yes	Yes	Yes	Yes	Yes	Yes



23

## PSU WRF



24


I © 2024 GHD. All rights reserved.

24



## PSU's use of an Owner Advisor


- Helped Manage and Mitigate Risks to PSU and Project team; identified solutions & strategy to mitigate
- Provided technical knowledge, contracts review, construction scope and pricing to meet PSU's project performance objectives
- Team was mindful of schedule, budget & quality objectives



25

## PSU's use of an Owner Advisor

- Quick, creative and decisive decision- making process to PSU
- Co-locating key team members with the Owner at meetings
- Deep bench of contracts, technical, construction, and commissioning staff
- Excellent Communication / Transparency with D/B and PSU



NORTH-WEST AXONOMETRIC

26

## Benefits of having OA

Experienced in  
Collaborative  
Delivery

Technical  
Expertise

Construction  
Experience

Risk  
Management

Startup and  
Operations

State and  
Local Statutes



Design and Treatment Performance



Administrative/Permit Performance



Delivery Performance (Construction)



Operational Performance



Life Cycle Performance

27

# QUESTIONS



28



**[www.ghd.com](http://www.ghd.com)**